

Change Order

PROJECT: (Name and address)

22210000

Linn-Mar Administration Building

3556 Winslow Road Marion, IA 52302

OWNER: (Name and address)

Linn-Mar Community School District

2999 North Tenth Street

Marion, IA 52302

CONTRACT INFORMATION:

Contract For: New Linn-Mar Administration Building

Date: June 5, 2023

CHANGE ORDER INFORMATION:

Change Order Number: 006

Date: March 8, 2024

ARCHITECT: (Name and address)

OPN Architects

200 5th Ave. SE, Suite 201 Cedar Rapids, IA 52401 CONTRACTOR: (Name and address)

Peak Construction Group 660 Liberty Way, Unit C

North Liberty, IA 52317

THE CONTRACT IS CHANGED AS FOLLOWS:

(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits. Also include agreed upon adjustments attributable to executed Construction Change Directives.)

COR 013.2 - ITC 013 FFE Power and Data Revisions

COR 014.1 - ITC 015 Acoustical Partitions

Total

\$4,309.50

\$16,715.95

\$21,025.45

The original Contract Sum was

The net change by previously authorized Change Orders

The Contract Sum prior to this Change Order was

The Contract Sum will be increased by this Change Order in the amount of

The new Contract Sum including this Change Order will be

The Contract Time will be unchanged by Zero (0) days.

The new date of Substantial Completion will be

NOTE: This Change Order does not include adjustments to the Contract Sum or Guaranteed Maximum Price, or the Contract Time, that have been authorized by Construction Change Directive until the cost and time have been agreed upon by both the Owner and Contractor, in which case a Change Order is executed to supersede the Construction Change Directive.

NOT VALID UNTIL SIGNED BY THE ARCHITECT, CONTRACTOR AND OWNER.

OPN Architects	
ARCHITECT (Firm name)	
5	

SIGNATURE

Dan Hammes, CA

PRINTED NAME AND TITLE

3/8/24

DATE

Peak Constuction Group

CONTRACTOR (Firm name)

SIGNATURE

Kris Chyko, President

PRINTED NAME AND TITLE

DATE

Linn-Mar Community School District

OWNER (Firm name)

SIGNATURE

Barry Bucholz, Board President

PRINTED NAME AND TITLE

DATE

Change Order Summary 3.8.24

New Linn-Mar Admin Building

COR Number	Title	RFI/ITC	AMOUNT	Description
13.3	Costs associated with ITC 013 - FFE power and data revisions	ITC 013	\$ 4,309.50	Power and data revisions to align with furniture, fixutures, and equipment layout.
14.1	Costs associated with ITC 015 - Acoustical Partitions	ITC 015	\$ 16,715.95	Providing acoustical partitions to deck and sound sealant.

Total: \$ 21,025.45



2/21/2024 CONSTRUCTION GROUP 023-014 Date: **Project:** Linn-Mar Administration Building COR # 013 rev. 2 To: **OPN Architects Peak Construction Group** From: Attn: Dan Hammes **Description:** Costs associated with ITC 013 **CONTRACTOR/VENDOR INFO** Amount Peak Material \$0.00 **Peak Equipment** \$0.00 \$0.00 Peak Labor Hawkeye Electric \$4,037.27

Notes:

 Subtotal
 \$4,037.27

 Peak OHP (10%)
 \$0.00

 Subcontractors OHP (5%)
 \$201.86

 Bond
 \$70.37

 Total
 \$4,309.50

Phone: 319-383-3474 Email: info@iowapeak.com

www.iowapeak.com

660 Liberty Way Unit C, North Liberty, IA 52317



Hawkeye Electric Change Order

Project:	Linn Mar Adn	nin		7	Tracking #:	ITC #13		
-	1.24.24				•			
	Description: Make Changes to the power and data rough in per ITC							
·		·						
General:	Peak	Attn: St	teve/Ethar	<u>1</u>	Material	Unit	Material	Labor
					Quantity	Cost	Total	Hours
					1		\$0.00	
					0	\$0.00	\$0.00	
					0	\$0.00	\$0.00	
					0	\$0.00	\$0.00	0.00
					1	\$0.00	\$0.00	0.00
Large Office					1	\$0.00	\$0.00	
Relocate AB-	-4				1	\$28.00	\$28.00	
Labor	10001				1	\$0.00	\$0.00	2.30
Large Office					1	\$0.00	\$0.00	
Relocate AB-	-4				1	\$28.00	\$28.00	2.30
Move DD 3'	1010				1	\$14.00	\$14.00	1.50
Open Office	1010				1	\$0.00	\$0.00	
Delete DD					1	005	\$0.00	1.00
Add Furnitue					1	\$95	\$95.00	1.50
Large Office					1	00	\$0.00	
Relocate AB-	-4				1	28	\$28.00	
Labor	10100				1		\$0.00	2.30
Large Office					1		\$0.00	
Relocate AB-	-4				1	28	\$28.00	
Labor	10100				1	ļ	\$0.00	2.30
Large Office					1	00	\$0.00	
Relocate AB-	-4				1	28	\$28.00	2.30
Labor	40445				1		\$0.00	
Large Office					1	00	\$0.00	
Relocate AB-	-4				1	28	\$28.00	0.00
Labor					1	00	\$0.00	2.30
Office 1029A					1	28	\$28.00	
Relocate AB-	-4				1		\$0.00	2.20
Labor					1	1201 10	\$0.00	2.30
Tri City Cabli	rig				-	1384.18	\$1,384.18	
							\$0.00	
					<u> </u>		\$0.00	20.10
	Material:	\$1,689.18					\$1,689.18 Materials	Labor Hrs
	Tax:	\$0.00		Hours	x Rate		iviaiciiais	Labul IIIS
For	reman Labor:	\$2,155.84	=	25.10	\$ 85.89			

Foreman Labor: \$2,155.84

Journeyman Labor: \$0.00

Apprentice Labor: \$0.00

OH/Profit: \$192.25 Sub-cont: \$0.00 OH/Profit: \$0.00 **Total:** \$4,037.27 25.10 \$ 85.89 0.00 \$ 80.76 0.00 \$ 72.38

A signed copy of this change order must be returned to Hawkeye Electric before any work will be performed. Please return within 5 days of receipt or additional charges may apply due to job progress.



INSTRUCTION TO CONTRACTOR - ITC NO. 013R

Date: February 09, 2024

Project: Linn-Mar Administration Building

Project Number: 22210000

Client: Linn-Mar Community School District

General Contractor: Peak Construction Group

If, in your opinion, this instruction involves work that either increases or decreases the Contract Sum or Contract Time, you **shall not proceed** until you submit a Change Authorization Request and receive signed authorization to proceed. Proceeding with the Work prior to authorization indicates your acknowledgement that there will be no change in the Contract Sum or Contract Time.

The following Instruction to Contractor is issued to:

- ⊠ Clarify drawings, specifications, and/or material selection.
- \square Request an estimate for Owner's further consideration.
- Transmit drawings or documents for incorporation into the work, subject to the above statement.

Initiated By: Owner

Description: Power and Data Revisions associated with the latest FFE plans approved by the Owner. Verification of scope of work with edits from the initial ITC 013 that went out as a request for an estimate for Owner's consideration - the changes originally included for offices 1001B and 1001C in ITC 013 have been removed from ITC 013R.

Action Required:

- 1. E211: ELECTRICAL POWER PLAN Refer to Reissued Sheet.
 - i. Large Office 1003B:
 - 1. REVISE location of AB-4 on the plan east wall further plan north to align with updated FFE plans.
 - 2. REVISE the duplex receptacle on the plan west wall to be a double duplex.
 - 3. REVISE the double duplex receptacle on the plan south wall to be a single duplex.
 - ii. Large Office 1006A:
 - 1. REVISE location of AB-4 to the plan north wall to align with updated FFE plans.
 - 2. REVISE the duplex receptacle on the plan south wall to be a double duplex. Shift device rough-in approximately 3' plan west.
 - 3. REVISE the double duplex receptacle on the plan north wall to be a single duplex.
 - iii. Open Office 1010:
 - DELETE the quantity two (2) double duplex receptacles on the plan north and plan east walls, respectively.
 - ADD a furniture feed power connection on the plan north wall, adjacent to the door sidelight. Circuit to LD-73.
 - iv. Large Office 1010B:
 - 1. REVISE location of AB-4 to the plan north wall to align with updated FFE plans.
 - 2. REVISE the duplex receptacle on the plan south wall to be a double duplex.
 - 3. REVISE the double duplex receptacle on the plan west wall to be a single duplex.
 - v. Large Office 1010C:
 - 1. REVISE location of AB-4 to the plan north wall to align with updated FFE plans.
 - 2. REVISE the duplex receptacle on the plan south wall to be a double duplex.
 - 3. REVISE the double duplex receptacle on the plan east wall to be a single duplex.



vi. Large Office 1010D:

1. REVISE location of AB-4 to the plan north wall to align with updated FFE plans.

vii. Large Office 1011E:

- 1. REVISE location of AB-4 on the plan west wall further plan north to align with updated FFE plans.
- 2. REVISE the duplex receptacle on the plan east wall to be a double duplex.
- 3. REVISE the double duplex receptacle on the plan north wall to be a single duplex.

viii. Large Office 1029A:

- 1. REVISE location of AB-4 to the plan west wall in lieu of plan north wall.
- 2. REVISE the duplex receptacle on the plan north wall to be a double duplex.
- 3. REVISE the double duplex receptacle on the plan south wall to be a single duplex.

2. T111: TECHNOLOGY PLAN - Refer to Reissued Sheet.

i. Large Office 1003B:

- REVISE location of wall activation box data on the plan east wall further plan north to align with revised activation box location.
- 2. REVISE the two data drops shown on the plan south wall to instead be on the plan west wall adjacent to the duplex receptacle being revised to a double duplex receptacle.

ii. Large Office 1006A:

- 1. REVISE location of wall activation box data to the plan north wall to align with revised activation box location.
- 2. REVISE the two data drops shown on the plan north wall to instead be on the plan south wall adjacent to the duplex receptacle being revised to a double duplex receptacle. REVISE quantity of drops to three (3) in lieu of two (2).
- 3. REVISE the three data drops shown on the plan west wall to quantity two (2) drops.

iii. Large Office 1010:

1. ADD a furniture feed data connection on the plan north wall, adjacent to the door sidelight. For clarification, the quantity four data drops in Open Office 1010 shall be routed through the furniture feed in lieu of directly terminated at the wall. Refer to the updated furniture plan.

iv. Large Office 1010B:

- 1. REVISE location of wall activation box data to the plan north wall to align with revised activation box location.
- 2. REVISE the two data drops shown on the plan west wall to instead be on the plan south wall adjacent to the duplex receptacle being revised to a double duplex receptacle.

v. Large Office 1010C:

- 1. REVISE location of wall activation box data to the plan north wall to align with revised activation box location.
- 2. REVISE the two data drops shown on the plan east wall to instead be on the plan south wall adjacent to the duplex receptacle being revised to a double duplex receptacle.

vi. Large Office 1010D:

- 1. REVISE location of wall activation box data to the plan north wall to align with revised activation box location.
- 2. REVISE the three data drops shown on plan north side of the plan east wall to instead be two (2) data drops.
- 3. REVISE the two data drops shown on the plan south side of the plan east wall to instead be quantity three (3) drops.

vii. Large Office 1011E:

- 1. REVISE location of wall activation box data on the plan west wall further plan north to align with revised activation box location.
- 2. REVISE the three data drops shown on the plan south wall to instead be two (2) data drops.
- 3. REVISE the two data drops shown on the plan north wall to instead be quantity three (3) drops on the plan east wall adjacent to the duplex receptacle being revised to a double duplex receptacle.



viii. Large Office 1029A:

- 1. REVISE location of wall activation box data to the plan west wall in lieu of plan north wall to align with revised activation box location.
- 2. REVISE the two data drops shown on the plan south wall to instead be on the plan north wall adjacent to the duplex receptacle being revised to a double duplex receptacle.

3. TA111: AUDIO VISUAL PLAN – Refer to Reissued Sheet.

- i. Large Office 1003B:
 - 1. REVISE location of LED-1, MNT-W, HRX-1 wall devices on the plan east wall further plan north to align with revised activation box location.
 - 2. REVISE location of HTX-1 device to the plan west wall to be adjacent to the duplex receptacle being revised to a double duplex receptacle.

ii. Large Office 1006A:

- 1. REVISE location of LED-1, MNT-W, HRX-1 wall devices to the plan north wall further to align with revised activation box location.
- 2. REVISE location of HTX-1 device to the plan south wall to be adjacent to the duplex receptacle being revised to a double duplex receptacle.

iii. Large Office 1010B:

- 1. REVISE location of LED-1, MNT-W, HRX-1 wall devices to the plan north wall to align with revised activation box location.
- 2. REVISE location of HTX-1 device to the plan south wall to be adjacent to the duplex receptacle being revised to a double duplex receptacle.

iv. Large Office 1010C:

- 1. REVISE location of LED-1, MNT-W, HRX-1 wall devices to the plan north wall to align with revised activation box location.
- 2. REVISE location of HTX-1 device to the plan south wall to be adjacent to the duplex receptacle being revised to a double duplex receptacle.

v. Large Office 1010D:

- 1. REVISE location of LED-1, MNT-W, HRX-1 wall devices to the plan north wall to align with revised activation box location.
- 2. REVISE location of HTX-1 device to the south end of the plan east wall. Device shall be adjacent to the southern double duplex receptacle on the east wall.

vi. Large Office 1011E:

- 1. REVISE location of LED-1, MNT-W, HRX-1 wall devices on the plan west wall further plan north to align with revised activation box location.
- 2. REVISE location of HTX-1 device to the plan east wall to be adjacent to the duplex receptacle being revised to a double duplex receptacle.

vii. Large Office 1029A:

- 1. REVISE location of LED-1, MNT-W, HRX-1 devices to the plan west wall in lieu of plan north wall to align with revised activation box location.
- 2. REVISE location of HTX-1 device by shifting approximately 9' plan east to be adjacent to the duplex receptacle being revised to a double duplex receptacle.


Associated RFIs:

None

Attachments:

E211, T111, TA111

Issued By: TMK - DE



200 5th Ave. SE, Suite 201

Cedar Rapids, IA 52401 P: 319-363-6018 F: 319-363-7349 www.opnarchitects.com All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by OPN Architects, Inc. as instruments of service shall remain

> Owner LINN-MAR COMMUNITY SCHOOL DISTRICT 2999 NORTH 10TH ST

LINN MAR ADMINISTRATION BUILDING

HALL & HALL ENGINEERS, INC

1860 BOYSON RD. HIAWATHA, IA 52233

Structural Engineer STRUCTURAL DESIGN GROUP, LLC 350 THIRD AVE SW, SUITE 101

CEDAR RAPIDS, IA 52404 P. 319-449-1368 Mechanical Engineer DESIGN ENGINEERS

8801 PRAIRIE VIEW LN. SW, SUITE 200 CEDAR RAPIDS, IA 52404 P. 319-841-1944

Electrical Engineer DESIGN ENGINEERS 8801 PRAIRIE VIEW LN. SW, SUITE 200 CEDAR RAPIDS, IA 52404 P. 319-841-1944

FOOD SERVICE CONSULTANT ADVANCED FOOD SERVICE


CONSULTING 6201 SOUTH GATEWAY DR MARION, IA 52302

ITC 005R ITC 005R

Sheet Issue Date

Sheet Name **ELECTRICAL POWER PLAN**

Sheet Number E211



1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 25 |

ALL CONDUIT SLEEVES ARE 2"
UNO


Sheet Issue Date

100% CDs

Sheet Name
TECHNOLOGY PLAN

Sheet Number

T111



1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 25 |

1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17

22210000

AUDIO VISUAL PLAN

TA111



023-014		Date:	2/28/2024 ^{CO}	NSTRUCTION GROUP
Project:	Linn-Mar Administration Building			
COR # 014 rev 1				
То:	OPN Architects	From:	Peak Constructi	on Group
Attn:	Dan Hammes			
Description:				
Costs associated with ITC 015	i e			
CONTRACT	OR/VENDOR INFO		_	Amount
Option #1:				
Young's Painting				\$10,400.00
Precision Drywall				\$5,260.00
			Peak OHP (5%)	\$783.00
			Bond	\$272.95
			TOTAL	\$16,715.95

Notes:

Phone: 319-383-3474 Email: info@iowapeak.com www.iowapeak.com 660 Liberty Way Unit C, North Liberty, IA 52317





To: Peak Construction

Project: Linn Mar Administration

Date: 2/28/24

Office Phone: 319-334-4786

Contact Name: Andrew Young

Contact Phone Number: 319-327-6966

Proposal:

Option # 1

Pricing for ITC-015 in regards to RFI 031

Price for adding spraying of USG Acoustical sealant to seal tops of framed walls to decking.

Does not include stuffing void with insulation, Precision is said to be doing this

Labor = \$6,500

Materials = \$3,900

Total = \$10,400

Phone: (319) 363-5616 Fax: (319) 363-6112



1011 2nd Ave. SW Suite 200 Cedar Rapids, IA 52404

BID PROPOSAL

Optin # 1

Prepared For: Peak Construction Group

Contact: Steve Oyen / Ashley Roeder

Date: 2/27/23

Linn-Mar Administration Building,

Marion, IA

COR #003- ITC#15 - Acoustical

Partitions (Kinzler)

COR#003: Extra cost for material and labor related to ITC #015 and includes the following, see below:

Material and Labor Breakdown Description:

Mineral Wool Batting – 3" SAFB 24"x48" – installed in top of walls that run left to right, shown with batting on the RCP plan

*** Price does not include any spray. Price is to stuff flutes only ***

Kinzler Proposal:

\$5,010.00

OHP-5%:

\$250.00

Materials and Labor for the Sum of:

ADD-\$5,260.00

(Five Thousand, Two Hundred and Sixty Dollars)

Notes:

- Due to the fluctuating steel prices, quote is subject to change if not accepted within 30 days.
- Topping out of gypsum board to happen before MEP installation, where applicable.
- Temperature and Humidity will need to be within the gypsum manufacturers standards before hanging and finishing of gypsum board will proceed. Building conditions is by others.

STANDARD EXCLUSIONS:

Expansion Joints Material and Labor Dust Partitions / Temporary Walls Spray Foam Insulation Insulation of any kind unless stated above Wood Framing / Construction Demolition Acoustical Ceilings **Dumpsters** Setting and Grouting HM Frames

Framing / Structure at Caseworks Prefinished Break Metal at Stud Walls Caulking of any kind Painting Plywood / OSB Fire Caulking

Weekend / Premium Time Bondina Fry Reglet (Other than Above) Permits and Fees

Wall Labeling / Stenciling (Painter) Level 5 Finish (Unable to Locate)

Foam Board Acoustical Caulking Backing & Blocking Fireproofing / Firesafing

Engineering / Shops (Other than above)

We do not provide heating, weather protection, fans, dehumidifiers, electricity, water, or lights.
We are not responsible for the clean-up of other trades. We are not responsible for damage to project by any other contractors. Owner's items in work area are sole responsibility of owner for theft or damage.
This proposal is good for 30 days, subject to change after 30 days for labor or material price changes.

PREPARED BY:	Will Clark	ACCEPTED BY:	
TITLE:	Project Manager / Estimator	TITLE:	
DATE:	2/27/2024	DATE:	



INSTRUCTION TO CONTRACTOR – ITC NO. 015

Date: January 29, 2024

Project: Linn-Mar Administration Building

Project Number: 22210000

Client: Linn-Mar Community School District

General Contractor: Peak Construction Group

If, in your opinion, this instruction involves work that either increases or decreases the Contract Sum or Contract Time, you shall not proceed until you submit a Change Authorization Request and receive signed authorization to proceed. Proceeding with the Work prior to authorization indicates your acknowledgement that there will be no change in the Contract Sum or Contract Time.

The following Instruction to Contractor is issued to:

- ☐ Clarify drawings, specifications, and/or material selection.
- Request an estimate for Owner's further consideration.
- Transmit drawings or documents for incorporation into the work, subject to the above statement.

INITIATED BY: Peak, OPN

DESCRIPTION: RFI 031 – Acoustical Partitions

GENERAL INFORMATION:

DRAWINGS

ARCHITECTURAL DRAWINGS

- 1. Sheet A701 REFLECTED CEILING PLAN
 - a. REISSUED full sheet to reflect acoustical partitions.


Associated RFIs: RFI 31

Attachments:

Architectural Sheets: A701

Issued By: Dan Hammes/OPN

END OF ITC NO. 015



A701

Sheet Number